

La Quebrada Viva — Bill of Quantities

Generated: **2026-06-13**

USD → PYG rate: **7,300 PYG / USD**

Per-module breakdown is in the companion Markdown file; this PDF carries the per-material rollup and grand total only.

Per-material rollup

material	total qty	unit	total USD	total PYG
lapacho_deck_planks	196.00	m2	\$22,860.00	Gs. 166,878,000
palm_thatch	529.51	m2	\$18,891.42	Gs. 137,907,366
shipping_container_20ft	5.00	count	\$17,500.00	Gs. 127,750,000
lapacho_deck	17.57	m3	\$17,389.15	Gs. 126,940,795
etfe_glass_dome_panels	56.55	m2	\$16,116.37	Gs. 117,649,503
stone_walls	58.50	m3	\$12,735.00	Gs. 92,965,500
concrete_service_spine	35.09	m3	\$10,907.80	Gs. 79,626,940
sandstone_foundation	30.50	m3	\$10,131.20	Gs. 73,957,760
bamboo_culm	1,147.90	m	\$10,027.40	Gs. 73,200,020
reflection_pool_basin_concrete	48.00	m2	\$7,920.00	Gs. 57,816,000
terracotta_tile_roof	184.00	m2	\$6,342.00	Gs. 46,296,600
lapacho_shutters_doors	39.00	m2	\$5,840.00	Gs. 42,632,000
lapacho_joinery	4.35	m3	\$5,649.80	Gs. 41,243,540
lapacho_timber	4.69	m3	\$5,577.15	Gs. 40,713,195
glass_glazing	26.92	m2	\$5,499.84	Gs. 40,148,832
reinforced_concrete_shell	14.08	m3	\$4,505.60	Gs. 32,890,880
guadua_deck_culms	600.00	m	\$3,600.00	Gs. 26,280,000
glass_river_wall	13.50	m2	\$3,240.00	Gs. 23,652,000
sandstone_coping_slabs	32.00	m	\$3,040.00	Gs. 22,192,000
stone_foundation	13.82	m3	\$2,876.80	Gs. 21,000,640
reflective_water_basin_liner	140.00	m2	\$2,520.00	Gs. 18,396,000
sandstone_pool_coping	32.00	m	\$2,496.00	Gs. 18,220,800
lapacho_dome_struts	65.00	m	\$2,470.00	Gs. 18,031,000
fasteners_lashings	2,033.00	count	\$2,433.50	Gs. 17,764,550
lapacho_communal_slab_table	1.00	count	\$2,200.00	Gs. 16,060,000
concrete_service_wall	6.89	m3	\$2,068.20	Gs. 15,097,860
concrete	6.84	m3	\$2,053.20	Gs. 14,988,360
sandstone_boulder_seating	14.00	count	\$1,960.00	Gs. 14,308,000
sliding_door_assembly	1.00	count	\$1,950.00	Gs. 14,235,000
plywood_lapacho_gable	39.00	m2	\$1,872.00	Gs. 13,665,600
cob_walls	19.48	m3	\$1,850.60	Gs. 13,509,380

material	total qty	unit	total USD	total PYG
pool_circulation_pump_filter	1.00	count	\$1,850.00	Gs. 13,505,000
rebar_steel	1,219.80	kg	\$1,768.71	Gs. 12,911,583
sandstone	5.52	m3	\$1,766.40	Gs. 12,894,720
sod_roof_grass	89.80	m2	\$1,616.40	Gs. 11,799,720
lapacho_deck_posts	48.00	count	\$1,616.00	Gs. 11,796,800
palm_thatch_roof	73.44	m2	\$1,615.68	Gs. 11,794,464
corten_cladding	32.00	m2	\$1,536.00	Gs. 11,212,800
lapacho_beams_porch	1.15	m3	\$1,455.00	Gs. 10,621,500
lapacho_catwalk_assembly	1.00	count	\$1,450.00	Gs. 10,585,000
yoga_shelter_frame	1.00	count	\$1,450.00	Gs. 10,585,000
bamboo_curtain_wall_culms	30.00	count	\$1,440.00	Gs. 10,512,000
stone_foundation_arched	4.50	m3	\$1,395.00	Gs. 10,183,500
curtain_textile	45.80	m2	\$1,282.40	Gs. 9,361,520
borax_boric_treatment	138.50	kg	\$1,214.50	Gs. 8,865,850
bamboo_pendant_lanterns	9.00	count	\$1,170.00	Gs. 8,541,000
loggia_paving	21.00	m2	\$1,155.00	Gs. 8,431,500
reflection_pool_water_treatment	4.80	m3	\$1,152.00	Gs. 8,409,600
solar_pv_panels	6.00	count	\$1,080.00	Gs. 7,884,000
ceramic_kitchen_tile	28.80	m2	\$1,036.80	Gs. 7,568,640
concrete_slab_plinth	5.75	m3	\$1,035.00	Gs. 7,555,500
glass_bowl_lanterns	9.00	count	\$990.00	Gs. 7,227,000
container_opening_cuts	4.00	count	\$960.00	Gs. 7,008,000
lapacho_window_frames	2.00	count	\$960.00	Gs. 7,008,000
steel_ibeam_piers	10.00	m	\$950.00	Gs. 6,935,000
lapacho_deck_planks	0.50	m3	\$900.00	Gs. 6,570,000
fasteners_misc	830.00	count	\$892.00	Gs. 6,511,600
lapacho_beams_columns	0.60	m3	\$870.00	Gs. 6,351,000
lapacho_deck_joists	36.00	m	\$864.00	Gs. 6,307,200
lapacho_door	2.00	count	\$860.00	Gs. 6,278,000
container_handling_set	1.00	count	\$850.00	Gs. 6,205,000
pv_glass_glazing	3.24	m2	\$777.60	Gs. 5,676,480
stool_set_bamboo_lapacho	8.00	count	\$760.00	Gs. 5,548,000
lapacho_railing_stair	0.40	m3	\$720.00	Gs. 5,256,000
pv_glass_clerestory	2.76	m2	\$717.60	Gs. 5,238,480
pool_excavation_combined	31.60	m3	\$695.20	Gs. 5,074,960
lapacho_bench_lounge	1.00	count	\$680.00	Gs. 4,964,000
lapacho_deck_boards	7.00	m2	\$665.00	Gs. 4,854,500
sandstone_stepping_stones	10.00	count	\$650.00	Gs. 4,745,000

material	total qty	unit	total USD	total PYG
mossy_boulders_lounge	2.00	count	\$640.00	Gs. 4,672,000
lapacho_entry_door	1.00	count	\$620.00	Gs. 4,526,000
pergola_lapacho_bamboo_frame	22.40	m	\$582.40	Gs. 4,251,520
lapacho_canopy_posts	4.00	count	\$580.00	Gs. 4,234,000
fasteners	680.00	count	\$578.00	Gs. 4,219,400
insulated_glazing_units	1.71	m2	\$547.20	Gs. 3,994,560
boulder_seat_stones	3.00	count	\$540.00	Gs. 3,942,000
lapacho_round_door	1.00	count	\$520.00	Gs. 3,796,000
outdoor_shower_assembly	1.00	count	\$480.00	Gs. 3,504,000
lapacho_floor_mat	18.10	m2	\$470.60	Gs. 3,435,380
pv_glass	1.96	m2	\$470.40	Gs. 3,433,920
guadua_roof_frame	58.08	m	\$464.67	Gs. 3,392,058
mosquito_mesh	35.00	m2	\$450.00	Gs. 3,285,000
low_voltage_lantern_wiring_set	1.00	count	\$420.00	Gs. 3,066,000
lashings_hardware	22.00	kg	\$396.00	Gs. 2,890,800
guadua_ring_beam_culms	33.60	m	\$369.60	Gs. 2,698,080
bamboo_shingle	20.00	m2	\$360.00	Gs. 2,628,000
palm_thatch_yoga_roof	16.16	m2	\$355.46	Gs. 2,594,853
sisal_rope_lashings	90.00	m	\$315.00	Gs. 2,299,500
surround_flora_clumps_saplings	4.00	count	\$300.00	Gs. 2,190,000
pergola_palm_thatch_roof	10.35	m2	\$289.80	Gs. 2,115,540
fasteners_hardware	350.00	count	\$280.00	Gs. 2,044,000
sandstone_cascade_weir	0.64	m3	\$243.20	Gs. 1,775,360
bamboo_accent	24.00	m	\$216.00	Gs. 1,576,800
rope_hemp	60.00	m	\$210.00	Gs. 1,533,000
lapacho_stair_treads	5.00	count	\$190.00	Gs. 1,387,000
mosquito_mesh_screen	4.10	m2	\$155.80	Gs. 1,137,340
suspended_walkway_cable	14.00	m	\$126.00	Gs. 919,800
guadua_columns	12.80	m	\$115.20	Gs. 840,960
stainless_mosquito_mesh	1.40	m2	\$30.80	Gs. 224,840

Grand total: \$268,685.45 · Gs. 1,961,403,785